BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/02/2020-21 Date: 10.06.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT42928

SCHEDULE -B

Name of Work: Improvements and resetting of damaged culverts and drains Jalahalli Village and surrounding area in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.
1	2	3	4	5	6
1	405.66	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. KSRB 2-2.2 : --do-- in hard soil.	Cum	480.00	Rupees Four Hundred Eighty Only
2	51.36	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	5780.00	Rupees Five Thousand Seven Hundred Eighty Only
3	154.08	KSRB 5.2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. - do - cement mortar 1:8	Cum	5050.00	Rupees Five Thousand Fifty Only
4	30.82	KSRB 4-1.7 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6000.00	Rupees Six Thousand Only
5	273.92	KSRB 15.1.3 – do – Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. KSRB 15.1.3 – do – cement mortar 1:3	Sqm	161.00	Rupees One Hundred Sixty One Only
6	44.10	Providing and fixing RCC pre cast cover slab of 250 mm for drain in cement concrete M20 using graded granite jelly 20mm and downsize with steel reinforcement, including formwork, lift charges, curing and concrete finished surfaces on both sides etc., complete as per drawing and the directions of Engineer in-charge. (Data rate)	Cum	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

7	275.00	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per pecifications.	Sqm	102.00	Rupees One Hundred Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP